

કાર્યપાલક ઈજનેર શ્રીની કચેરી,
સરદાર કૃષિનગર દાંતીવાડા કૃષિ યુનિવર્સિટી,
સરદાર કૃષિનગર.


—:: પ રિ પ ત્ર ::—

આથી સરદાર કૃષિનગર દાંતીવાડા કૃષિ યુનિવર્સિટી, સરદાર કૃષિનગર હસ્તકના તમામ યુનિટ / સબ યુનિટ કચેરી વડાશ્રીઓને જણાવવાનું કે યુનિવર્સિટી ખાતેની તમામ કચેરીઓ માટે રીપેરીંગ/રીનોવેશન/ સપ્લાયની માલ-સામાન મંજૂરી સાથેની કામગીરી કરાવવા માટે ઓન લાઈન ઈ-ટેન્ડરીંગથી ભાવો મંગાવવામાં આવેલ હતા. જે ભાવો સક્ષમ કક્ષાએથી મંજૂર કરવામાં આવેલ હોઈ માર્ચ-૨૦૨૧ સુધી અથવા તો જ્યાં સુધી નવીન ભાવો મંગાવવામાં ન આવે ત્યાં સુધી સામેલ લીસ્ટ મુજબની કામગીરી જે ઠેકેદારોના ભાવો મંજૂર થયેલ છે તેઓની પાસેથી કરાવવાની થાય છે.

વધુમાં જણાવવાનું કે, યુનિવર્સિટી ધ્વારા દરેક બીલમાંથી સરકારશ્રીના નિયમો મુજબ ૧% જી.એસ.ટી, ૧% સી.એસ.ટી, ૨% ઈનકેમ ટેક્સ, ૧% લેબર શેષ, ૧% મટીરીયલ ટેસ્ટીંગ તથા જ્યાં પાણીનો ઉપયોગ કરેલ હોય ત્યાં ૧% વોટર ચાર્જની કપાત કરવાની રહેશે. તેમજ એક કામગીરીના ઓર્ડરની રકમ વધુમાં વધુ રૂં. ૫.૦૦ લાખ સુધીની રહેશે. જે તે વિભાગની જરૂરીયાત તેમજ ઉપલબ્ધ ગ્રાન્ટની મર્યાદામાં સક્ષમ કક્ષાએથી મંજૂરી મેળવી કામગીરી કરાવવાની રહેશે. તેમજ કાર્યપાલક ઈજનેર કચેરી ધ્વારા અંદાજપત્રક તથા પ્રમાણપત્ર મેળવવાનું રહેશે. સદર ભાવો યુનિવર્સિટીની વેબસાઈટ [www.sdau.edu.in/ tender](http://www.sdau.edu.in/tender) ઉપર મુકવામાં આવેલ હોઈ તે ઉપરથી જરૂરીયાત મુજબની કામગીરી કરાવવા વિનંતી છે.

સદર પરિપત્ર અત્રેની કચેરીની તા.૩૦-૯-૨૦૨૦ની નોંધ પર મા.કુલપતિશ્રીની મંજૂરી મેળવી બહાર પાડવામાં આવે છે.

જા.નં:સદાંકૃયુ/કાઈ/ટી.૧૦/૨૮૫૭-૨૫૦૨ /૨૦
તારીખ:૨૨/૧૦/૨૦૨૦


સચિવ ઈજનેર

નકલ સવિનય રવાના :-

- ૧: કુલપતિશ્રીના રહસ્ય સચિવશ્રી, સ.દાં.કૃ.યુ., સરદાર કૃષિનગર તરફ જાણ સારું.
- ૨: સંશોધન નિયામકશ્રી, સ.દાં.કૃ.યુ., સરદાર કૃષિનગર તરફ જાણ સારું.
- ૩: વિસ્તરણ શિક્ષણ નિયામકશ્રી, સ.દાં.કૃ.યુ., સરદાર કૃષિનગર તરફ જાણ સારું.
- ૪: યુનિવર્સિટીના તમામ યુનિટ / સબ યુનિટ અધિકારીશ્રીઓ તરફ જાણ સારું.

ITEM RATE FOR REPAIRING & RENOVATION & SUPPLY WORK FOR S.D.A.U., @ S.K.NAGAR.

ITEM NO.	Item Description	QTY.	Unit	L.1. RATE	L.1 PARTY
1	Providing and laying cement concrete M-200 1:1.5:3 (1 cement : 1.5 coarse sand : 3 aggregates 20 mm thick. black trap kapchi) and curing complete for R.C.C road work including trimix.	1.00	CMT	4000.00	Krimal Infrastructure, Deesa
2	Providing and laying cement concrete M-150 1:2:4 (1 cement : 2 coarse sand : 4 aggregates 20 mm thick. black trap kapchi) and curing complete for R.C.C road work including trimix. (Only RMC material use.)	1.00	CMT	3400.00	Krimal Infrastructure, Deesa
3	Providing and laying cement concrete M-200 1:1.5:3 (1 cement : 1.5 coarse sand : 3 aggregates 20 mm thick. black trap kapchi) and curing complete for R.C.C road work including trimix. (Only RMC material use.)	1.00	CMT	4498.00	NANDINI INFRASTRUCTURE, Palanpur
4	Providing and laying cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 machine crushed stone aggregates 40 mm. nominal size) and curing complete excluding cost of form work in foundation and plinth.	1.00	CMT	2200.00	J. B. Solanki, Moti Mahudi
5	Providing and Laying cement concrete M-150 (1 cement : 2 coarse sand : 4 aggregates 20 mm thick. black trap kapchi) including finishing smooth with curing complete including the cost of plywood shuttering form work but excluding the cost of reinforcement ,concrete work in foundation FOOTING and mass concrete. Rate are also inclusive of Providing and mixing Plasticizer of approved make in proportion prescribed by Manufacturer.	1.00	CMT	3354.21	CHARVI CONST., palanpur
6	Providing and Laying cement concrete M-200 1:1.5:3 (1 cement : 1.5 coarse sand : 3 aggregates 20 mm thick. black trap kapchi) including finishing smooth with curing complete including the cost of plywood shuttering form work but excluding the cost of reinforcement ,concrete work in foundation FOOTING and mass concrete. Rate are also inclusive of Providing and mixing Plasticizer of approved make in proportion prescribed by Manufacturer.	1.00	CMT	3700.00	D.J.Chavda Const. co, Deesa
7	Providing and Laying cement concrete M-200 1:1.5:3 (1 cement : 1.5 coarse sand : 3 aggregates s 20 mm thick. black trap kapchi) including finishing smooth with curing complete including the cost of plywood shuttering form work but excluding the cost of reinforcement ,concrete work for R.C.C COLUMN AND BEAM/G.B. FOR GROUND FLOOR. Rate are also inclusive of Providing and mixing Plasticizer of approved make in proportion prescribed by Manufacturer.	1.00	CMT	5199.00	H. R. VAGDODA, Gadh
8	Providing and Laying cement concrete M-200 1:1.5:3 (1 cement : 1.5 coarse sand : 3 aggregates 20 mm thick. black trap kapchi) including finishing smooth with curing complete including the cost of plywood shuttering form work but excluding the cost of reinforcement ,concrete work for R.C.C SLAB FOR GROUND FLOOR. Rate are also inclusive of Providing and mixing Plasticizer of approved make in proportion prescribed by Manufacturer.	1.00	CMT	5200.00	D.J.Chavda Const. co, Deesa

9	Providing and Laying cement concrete M-150 (1 cement : 2 coarse sand : 4 aggregates 20 mm thick. black trap kapchi) including finishing smooth with curing complete including the cost of plywood shuttering form work but excluding the cost of reinforcement ,concrete work for R.C.C PARDI FOR GROUND FLOOR. Rate are also inclusive of Providing and mixing Plasticizer of approved make in proportion prescribed by Manufacturer.	1.00	CMT	5600.00	PUJAN BUILDCON Ahmedabad
10	Providing and Laying cement concrete M-200 1:1.5:3 (1 cement : 1.5 coarse sand : 3 aggregates 20 mm thick. black trap kapchi) including finishing smooth with curing complete including the cost of plywood shuttering form work but excluding the cost of reinforcement ,concrete work for R.C.C PARDI FOR GROUND FLOOR. Rate are also inclusive of Providing and mixing Plasticizer of approved make in proportion prescribed by Manufacturer.	1.00	CMT	6000.00	J. B. Solanki, Moti Mahudi
11	Providing & Laying twisted TMT Bar reinforcement (as per is code Fe-500) of approved make for RCC work including cleaning, bending, binding and placing in position with 16 gauge annealed wires etc. completed as per detailed structural drawing & details directed by E.I.C. for all floors	1.00	KG	48.00	J. B. Solanki, Moti Mahudi
12	PROVIDING AND LAYING BRICK MASONRY WORK AND PLASTER WORK P/L BRICK WORK using common burnt clay building bricks having crushing strength not less than 35 Kgs. / Sq. cm. In Super structure in foundation and above plinth level up to floor two level. Conventional bricks in Cement Mortar (1:6) (1 Cement : 6 coarse sand) for GROUND FLOOR. including filling and racking properly the joints and curing etc completes directed by E.I.C.	1.00	CMT	3100.00	D.J.Chavda Const. co, Deesa
13	Providing & laying half brick work using best available well burnt bricks having minimum crushing strength of 35 kg./sq cm in cement mortar 1:4 (1 cement:4 coarse sand) in super-structure and curing including scaffolding etc. complete.(a) Ground floor including filling and racking properly the joints and curing etc complete as directed by E.I.C.	1.00	SMT	449.00	NANDINI INFRASTRUCTURE, Palanpur
14	Uncoursed Rubble Masonry with hard stone of approved quality in foundations and plinth in Cement Mortar 1:6 (1- cement : 6-coarse sand including levelling up etc. complete (upto 10 ton)	1.00	CMT	2500.00	J. B. Solanki, Moti Mahudi
15	Providing 20mm thick sand faced cement plaster in two coats under layer 12mm thick cement plaster 1:3 (1 cement : 3 coarse sand) with 8mm thick cement plaster 1:1 (1 cement : 1 coarse sand) by Gutka on brick surface/ concrete surface including necessary scaffolding, watering etc. complete	1.00	SMT	220.00	J. B. Solanki, Moti Mahudi
16	Providing and Laying 20 mm thick machine cut mirror polished jet black granite Flooring/ skirting risers over 20mm thick base of c.m 1:5 (1:cement :5 coarse sand) including pointing with 1:2 (1cement : 2 stone dust) etc. Complete.(20 mm thick)	1.00	SMT	2400.00	J. B. Solanki, Moti Mahudi

17	Providing & Laying joint free type ceramic tiles of 8 mm thick and of required size in Flooring/ skirting treads of steps and landings laid on a bed of 12 mm thick cement mortar 1:3 (1 Cement : 3 coarse sand) finished with flush pointing in white ceand & Jointed with white cement slurry with type and shade as per architect choice. Make should be AGL, Somany Or Simpolo	1.00	SMT	596.00	Krimal Infrastructure, Deesa
18	Providing and laying 24" X 24" matt or glossy Vetrified 10 mm thick tile flooring over 20mm (ave) base of C.M. 1:6 on new surface or fixing on existing flooring by adhesive material incl. dismantling of existing flooring and jointed with colour cement-slurry incl. finished with flush pointing & cleaning the surface etc. comp. for light shed or dark shed. Make should be AGL, Somany Or Simpolo	1.00	SMT	650.00	CHARVI CONST., palanpur
19	Providing & laying rough chiselled dressed stone slab flooring 25mm thick over 20mm. (average) thick C.M. 1:6 (1: Cement : 6: coarse sand) base laid over and jointed with gray cement slurry mixed with pigment to match the shade of the slab including rubbing and finishing as per pattern.	1.00	SMT	301.00	Krimal Infrastructure, Deesa
20	Providing and fixing 3mm thick PVC carpet flooring including fixing by adhesive material approved design colour shed quality etc complete as directed by EIC.	1.00	SMT	150.00	CHARVI CONST., palanpur
21	Providing & fixing 8mm thick wooden flooring with MDF Base including fixing by adhesive material of approved design colour shed quality etc complete as directed by EIC.	1.00	SMT	2000.00	PUJAN BUILDCON Ahmedabad
22	PROVIDING AND LAYING COLOUR WORK Providing & Applying Painting with Three coat Plastic emulsion paint of approved brand & manufacture & required shade on wall and ceiling surfaces to give an even shade over & including a priming coat with a primer of approved brand & manufacture after thoroughly Brushing the surface free from mortar dropping & other foreign matter & also including preparing surface with birla white cement based putty mirror polished even & sand papered smooth. Make- Asian, Nerolac,Nipone	1.00	SMT	55.00	Krimal Infrastructure, Deesa
23	Providing & Applying all weather proof exterior acrylic emulsion paint (two coat) over one coat of exterior emulsion primer (one coat) .paint shall be APEX paint of Asian, Nerolac, Nipone make .give even shade after toughly brooming the surface to remove all dirt, dust and other matter drop etc. complete.	1.00	SMT	65.00	Krimal Infrastructure, Deesa
24	Providing & Applying priming coat over new steel and other metal surface after over and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter and scoured with brushes fine steel wool, scrapers and sand paper with ready mixed priming paint brushing red lead AND Painting two coats over it with enamel paint brushing, interior to give an even shade including cleaning the surface of all dift, dust and other foreign matter Make- asian,nerolac	1.00	SMT	65.00	Krimal Infrastructure, Deesa

25	PROVIDING AND LAYING PLUMBING & SENETARY WORK Providing & laying in wall ,ceiling and floor UPVC of 50 mm nominal bore, tube fitting and clamps and including excavation for trenches and refilling etc if necessary in case of floor trenches, including making good the wall ceiling and floor etc. complete as directed by E.I.C. Make should be Astral, Prince or Finolex	1.00	RMT	250.00	PUJAN BUILDCON Ahmedabad
26	Providing & laying in wall ,ceiling and floor UPVC of 40 mm nominal bore, tube fitting and clamps and including excavation for trenches and refilling etc if necessary in case of floor trenches, including making good the wall ceiling and floor etc. complete as directed by E.I.C. Make should be Astral, Prince or Finolex	1.00	RMT	190.00	PUJAN BUILDCON Ahmedabad
27	Providing & laying in wall ,ceiling and floor UPVC of 25 mm nominal bore, tube fitting and clamps and including excavation for trenches and refilling etc if necessary in case of floor trenches, including making good the wall ceiling and floor etc. complete as directed by E.I.C. Make should be Astral, Prince or Finolex	1.00	RMT	125.00	PUJAN BUILDCON Ahmedabad
28	Providing & laying in wall , ceiling and floor UPVC of 15 mm nominal bore, tube fitting and clamps and including excavation for trenches and refilling etc if necessary in case of floor trenches, including making good the wall ceiling and floor etc. complete as directed by E.I.C. Make should be Astral, Prince or Finolex	1.00	RMT	100.00	PUJAN BUILDCON Ahmedabad
29	Providing, Laying and jointing (to level or slopes) 110mm internal diameter PVC pipes of working pressure 10 Kg/sq.cm. for Vertical drainage-line including necessary fitting such as bends, tees, clamps, rubber packing ring..... etc. testing of pipe line, jointing with adhesive solvent cement including cost of jointing materials and all other necessary fixtures, fitting air and water tight testing the line including cutting and making floors walls as per original etc. complete as directed by E.I.C.Make should be Astral, Prince or Finolex	1.00	RMT	333.00	CHARVI CONST., palanpur
30	Providing and fixing SWR UPVC nanhi trap of self cleaning design with sand cast iron screwed down of hinged grating with/ without vent arm complete incl. cost of cutting and making good the walls & floors. (100mm inlet & 75mm outlet) Of standard company make approved by EIC	1.00	NO	150.00	CHARVI CONST., palanpur
31	Providing and fixing wash down white vitreous china WALL HUNG water closet W/C PAN of size 555x360x390mm with integral "P" or "S" trap including jointing the trap with pan and soil pipe in vitreous china white colour of Parryware, Hindware or cera make as selected by EIC. Rate inclusive of providing and fixing seat cover of the same make.	1.00	NO	6000.00	D.J.Chavda Const. co, Deesa
32	Providing and fixing bevell edge 6mm mirror of superior Glass (of approved quality)complete with base of 19mm thik. comm. plywood fixed to wooden cleats with C.P. brass screws & washers. Glass should be fixed with s.s. studs with the ply.	1.00	SMT	600.00	J. B. Solanki, Moti Mahudi
33	Providing and fixing C.P. brass PILLAR cock of approved quality (weight of bib cock shall not be less than 400 grams) (a) 15mm nominal bore. of Plumber, Hindware, cera or as directed by EIC	1.00	NO	900.00	Krimal Infrastructure, Deesa

34	Providing and fixing gun metal full way handle valve wof approved quality (screwed end)(c) 40 mm dia Of standard company make approved by EIC	1.00	NO	900.00	PUJAN BUILDCON Ahmedabad
35	Providing, laying and jointing PVC pipes of 10 kg/cm2 including excavation, back filling, testing of pipes and joints etc.(a) 100mm dia Of standard company make approved by EIC	1.00	NO	250.00	PUJAN BUILDCON Ahmedabad
36	Providing, laying and jointing PVC pipes of 10 kg/cm2 including excavation, back filling, testing of pipes and joints etc.(b) 150mm dia Of standard company make approved by EIC	1.00	NO	345.00	PUJAN BUILDCON Ahmedabad
37	Providing and fixing square mouth S.W. gully trap grade "A" complete with C.I. Grating brick masonry chamber and water tight C.I. Cover with frame of 300 X 300 mm size, (inside). The weight of cover to be not less than 4.5kg and frame to be not less than 2.70kg) as/ standard design. 100x150mm size "P" type.	1.00	NO	1300.00	PUJAN BUILDCON Ahmedabad
38	Providing and Fixing two layer white PVC WATER TANK of required Capacity of SINTEX or equivalent approved by EIC make including cost of all brass fixtures & fittings required as per given detail for inlet and outlet connection, air vent, cover, testing etc., all completed as per directed by E.I.C. 1.00	1.00	LITRE	7.99	H. R. VAGDODA, Gadh
39	Providing and fixing stainless steel kitchen sink of Nirali or Navkar make with overall size 535mm x 460mmx 200mm deep having bowl size 460mm x 385mm x 200mm with cement mortar 1:3 etc. complete. Rates Inclusive of 32 mm dia.CP brass waste coupling and 32 mm dia rigid pvc waste pipe up to. N.T.	1.00	NO	1999.00	NANDINI INFRASTRUCTURE, Palanpur
40	Providing and fixing stainless steel Laboratory sink of Nirali or Navkar make with overall size 535mm x 460mmx 200mm deep having bowl size 460mm x 385mm x 200mm with cement mortar 1:3 etc. complete. Rates Inclusive of 32 mm dia.CP brass waste coupling and 32 mm dia rigid pvc waste pipe up to. N.T.	1.00	NO	2200.00	J. B. Solanki, Moti Mahudi
41	PROVIDING JCB MACHINE Providing J.C.B Machine with GPRS system for excavation work and site cleaning work as per requirement(Charge will be paid as per on site work only)	1.00	HOUR	748.00	NANDINI INFRASTRUCTURE, Palanpur
42	PROVIDING AND FIXING MISCELLANEOUS WORK Providing and fixing M.S GRILL/GATE fabricated from MS flat, square bars , round bars, any shape, plates as per details including welding and two coats of oil paints on a primer coat of approved shade and quality etc. complete.	1.00	KG	68.00	CHARVI CONST., palanpur
43	Providing and Laying china mosaic water proofing treatment on terrace with glazed tiles pieces including 40 mm thk cc 1:2:4 bedding (IPS) including mixing of water proofing compound and top finished with 20 mm cement plaster in cement mortar 1:6 (1 cement: 6 coarce sand) jints with white cement, cleaning the surface, finishing, proper slope, curing etc. complete as directed by E.I.C. Rate including ten years performance of guarantee bond to be given on 100/- Rs stamp paper. (No extra shall be paid for variation in thickness.) including dismantling existing water proofing disposal as directed by EIC.	1.00	SMT	410.00	D.J.Chavda Const. co, Deesa

44	P/F ACP wall Panelling Providing and Fixing 4mm thick external grade aluminium composite panel over plaster with ms frames of 35 x 25 MS Pipe with two coat primer as directed by Engineer - in - charge properly screwed over plaster. ACP should be properly fixed and screwed with the frame and all joints to be filled and finished with silicone in pattern suggested by the architect with tray system. Colours also should metallic or any colour be selected as per architects instructions. rate includes acp, ms frame, fixtures, fittings, scaffolding, etc. complete . (ACP work)	1.00	SMT	1600.00	CHARVI CONST., palanpur
45	Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontals & verticals fixed over G.I. framework as specified by India Gypsm Co. or Gyptech. including trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1â€ x 1â€ for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note:- Only the plan area will be measured for payment. No extra payment will be made for cut outs, grooves, mouldings etc.)	1.00	SMT	667.00	CHARVI CONST., palanpur
46	Providing & fixing in Sintex PVC false ceiling of approved colour and design fixed over Aluminium pipe framework as specified by India Gypsm Co. or Gyptech. including trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1â€ x 1â€ for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.	1.00	SMT	860.00	CHARVI CONST., palanpur
47	Providing & fixing G.I corrugated sheet of approved quality 0.60mm thick brand design on existing structure with necessary nutt bolt, hooks, wishers etc complete directed by EIC. 0.60 mm thick.	1.00	SMT	700.00	D.J.Chavda Const. co, Deesa
48	PROVIDING AND FIXING DOOR & WINDOW WORK P/F FULLY GLASS ALLU. DOOR. mat/glossy finished colored, 15 micron anodised aluminium section made from aluminium glazed door of frame section 20048 x (63.50 x 38.10 x 2.0=1.30 kg/mt), shutter hinge side section and vertical style sections (85x 44.45 x 1.80 = 1.30 kg/mt) Weight with 8 mm thick toughen reflective glass (saint gobain / modi) make quality with glazing Patti, rubber packing including brass pivot hinges, floor spring, handles with locking arrangement etc. complete with mat / glossy finished colored anodised fixtures and fastenings, vertical and horizontal hollow frame section totally filled with non-teak wooden batten. etc complete as per directed by EIC and architect drawings.	1.00	SMT	3200.00	D.J.Chavda Const. co, Deesa
49	P/F Front toughen glass door Providing and fixing fully glass door with patch fitting door. Door shall consists of 12mm thick PLAIN toughened float glass (saint Gobin) fixing with necessary designer film, approved locking system, ss screws, gasket & heavy duty floor springs and 25mm dia ss full length door handles pair as selected as per architectural detailed drawings and specifications and as directed by E.I.C.	1.00	SMT	2200.00	CHARVI CONST., palanpur

50	Providing and fixing 30mm thick solid core flush door (with both side decorative teak veneer 4 mm thick .of approved make) with 8mm thick glass panel and finished with PU polish and fixed with granite framing with 150mm ss hinges and ss screws (four nos. per door) including as per architects instruction etc. complete.	1.00	SMT	3300.00	Balaji Furniture, Palanpur
51	Providing and fixing window having extruded aluminium color anodized section frame main outer size 95mmx24mmx1.17mm (of jindal section no: 2459 @ wt. of 0.738 kg/mt), horizontal three track member size 92mmx31.75mmx1.30mm (of jindal section no.: 8688; @ wt. 1.07 kg/mt), vertical member of size 92mmx31.75mm x1.50mm (of jindal section no: 8933, @ wt. 1.06 kg/mt) with sliding shutters of horizontal member size 40mmx 18mmx 1.29mm(of jindal section no.: 8947; @ wt. 0.456 kg/mt) vertical member of size 40mmx 18mmx 1.29mm(of jindal section no.: 8949; @ wt. 0.456 kg/mt) with 5mm thick transparent bronze colour tinted float glass with colour anodized aluminium fittings and fixtures and transparent silicon sealant glass fixing to frame as per detail. also, one third of total shutters should be having ss 316 mosquito jali shutter in each window, including required bearing concealed handel, anodized screws, wall fixtures and fastening and Alu.cleats etc. complete.	1.00	SMT	2500.00	D.J.Chavda Const. co, Deesa
52	Providing & Fixing color anodized Alu. glass Louveres & movable / fixed type ventilator with alu. (make banco / jindal) pipe Framing having pipe section RET-202060 (50.00 X 25.00 X 2.30 mm , wt. 0.873 kg/RMT. Including fixing anodized alu. Louvers patti of required size and approved quality with 5 mm thk. & 100 mm wide kasumbi/bajari glass as panel, including anodized screws, necessary fittings etc. complete. as directed by EIC	1.00	SMT	2200.00	D.J.Chavda Const. co, Deesa
53	Providing & fixing 35mm thick teak wood shutter door of required size and pattern of fully panelled in existing frame with necessary screw, hinges include one coat of primer and 2 coat of approved quality oil paint etc complete.	1.00	SMT	2799.00	H. R. VAGDODA, Gadh
54	Providing & fixing 35mm thick teak wood shutter window of required size and pattern of partly panelled and partly glazed in existing frame with necessary screw, hinges include one coat of primer and 2 coat of approved quality oil paint etc complete.	1.00	SMT	2901.00	H. R. VAGDODA, Gadh
55	Providing & fixing 35mm thick teak wood shutter Ventilation of required size and pattern of fully glazed in existing frame with necessary screw, hinges include one coat of primer and 2 coat of approved quality oil paint etc complete.	1.00	SMT	2901.00	H. R. VAGDODA, Gadh
56	Providing & fixing wood work frame of 10 X 7cm or 12 X 7cm for door including 35mm thick teak wooden shutter door of required size and pattern of fully panelled in existing frame with necessary screw, hinges include one coat of primer and 2 coat of approved quality oil paint etc complete. including the dismantling existing frame and do necessary masonry work and smooth plaster.	1.00	SMT	4800.00	H. R. VAGDODA, Gadh

57	Providing & fixing wood work frame of 10 X 7cm or 12 X 7cm for window including 35mm thick teak wooden shutter window of required size and pattern of fully panelled in existing frame with necessary screw, hinges include one coat of primer and 2 coat of approved quality oil paint etc complete. including the dismantling existing frame and do necessary masonry work and smooth plaster.	1.00	SMT	4500.00	Krimal Infrastructure, Deesa
58	Providing qualified PLUMBER for office time wok (Time 08am to 12am and 02pm to 06pm) payment done by contractor government norms. university not be responsible for any payment or dispute.	1.00	PER DAY	898.00	NANDINI INFRASTRUCTURE, Palanpur
59	PROVIDING AND SUPPLY MATERIAL Supply of precast Pavour block, rubber moulding & Lustre sinning of approved quality, shape, size and colour for construction work at require site in S.K.Nagar. A. 60 mm thick, M200	1.00	SMT	298.00	NANDINI INFRASTRUCTURE, Palanpur
60	b. 75 mm thick, M200	1.00	SMT	398.00	NANDINI INFRASTRUCTURE, Palanpur
61	Supply of un coursed rubble for construction work at require site in S.K.Nagar Campus.	1.00	CMT	798.00	NANDINI INFRASTRUCTURE, Palanpur
62	Supply of sand for construction work at require site in S.K.Nagar Campus.	1.00	CMT	298.00	NANDINI INFRASTRUCTURE, Palanpur
63	Supply of B.T. kapchi of 20 mm size for construction work at require site in S.K.Nagar Campus.	1.00	CMT	1000.00	D.J.Chavda Const. co, Deesa
64	Supplying EMPTY tractor with trolly for transportation of any type of material (without Labour) (only driver is required)	1.00	Hour	350.00	PUJAN BUILDCON Ahmedabad
65	Providing corrugated Powder coated G.I. sheets roofing fixed with galvanized iron "J" or "L" hooks bolts and nuts 8 m. diameter with bitumen and G.I. limpet washers filled with white lead complete excluding the cost of purling, rafters and trusses. (1) 0.60 mm thick sheet	1.00	smt	625.00	D.J.Chavda Const. co, Deesa
66	Steel work welded in built up sections, framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint :-(A) In beams and joints channels angles, tees, flats with connecting cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like etc.	1.00	kg	65.00	D.J.Chavda Const. co, Deesa
67	Providing, Laying & Fixing 3mm thick Solid Carbonate Sheet on fixing of 1" x 1" square pipe frame opening 0.60x0.60 m in slope with vertical frame covered by mosquito jail with M.S. patti & screw nails. Frame coloured with one coat red lead paint & two coat of synthetic enamel oil paint in true line & level etc complete as directed by E.I.C.	1.00	smt	555.50	H. R. VAGDODA, Gadh

68	Fixing Chain link jail 3"x3" opening size and 12 gauge including fixing the chain link jail on top side with M.S. 25 mmx6mm thick patti with M.S. angle with necessary nut bolts screws including P/F M.S. angle 40mmx40mmx6mm at 2.50 mtr centre to centre spacing and fixing the angle post in c.c. 1:2:4 coping with 2 nos. 8 mm TMT bar with 6 mm M.S. stimps 30 cm c/c including p/c conventional brick masonry 23 cm wall thickness and 1'-6" above ground level and 1'-6" below ground level with 23 cm thick brick masonry 2 layer including p/l PCC 1:4:8 mix x 4"thick and excavation of trench 1'-6"x1'-6"x1'-10" size including plastering the walls either side in c.m. 1:4 15 mm thickness including painting the M.S. angle post 40x40x6m, 6' height with necessary approved brand colour shade including white washing on walls etc. complete as directed by engineer in charge.	1.00	rmt	680.00	H. R. VAGDODA, Gadh
69	Providing and construction chain link fencing compound wall in brick masonry work including excavation 3" x 3" , P.C.C. 1:4:8 (4" thick) brick masonry work in foundation and 2" height (9" thick) above ground level, coping 6" thick, TMT steel work (Fe-500),15 mm thick cement plaster (1:4), chain link fencing having height 1.5 mtr above brick masonry, G.I chain link of approved quality 2" x 2" mesh fixing with 40x40x6mm MS angle (7" height) fixing in coping / bed block , two coats of oil paints, 2 row of barbered wire fencing , fixing in M.S. flate 25x6 mm at top including white washing 3 coat as per site condition and detail drawing as directed by engineer in charge.	1.00	rmt	680.00	H. R. VAGDODA, Gadh
70	P/S T.M.T. steel Fe500, requirement of approved quality & required size @ site.	1.00	kg	50.00	D.J.Chavda Const. co, Deesa
71	Steel work welded in built up section using MS angles, beams, flats as per detail design, drawings including priming coat & 2 coats of synthetic enamel oil paint etc. complete	1.00	kg	66.00	D.J.Chavda Const. co, Deesa
72	P/S & laying chemical water proofing treatment to terrace of approved quality , ISI manufacturing the surface, filling the cracks with Acrasill Chemical including laying fixing glass fabrics net / sheet with easy coat primer chemicals as per detail instruction & specification & method of application	1.00	smt	350.00	D.J.Chavda Const. co, Deesa

NAME OF AGENCY AND ADDRESS :

NANDINI INFRASTRUCTURE, DEV DARSHARN, MEHUL PARK, OPP. CIECUIT HOUSE, Palanpur Mo: 9408501611	Krimal Infrastructure, 08, indraprasth Nagar, Opp. Dantiwada colony, High-way, Deesa Mo: 9601996002
Balaji Furniture, 5, Bharat Society, B/h, Circuite House, Abu Highway, Palanpur Mo:9426896218	J. B. Solanki, At: Moti Mahudi, Ta. Dantiwada, Dist: B.K. Mo: 9979162303
CHARVI CONSTRUCTION, Sukhbag Road, Rabari Vas, Sonal Society, Palanpur Mo: 9898927002	D.J.Chavda Const. Co., Nakodaji Society, Nr. Shiv Temple, Opp. Kachchi colony, Deesa Mo: 9228112254
H. R. VAGDODA, At: & Po: Kumbhasan, Ta. Palanpur, Dist: Banaskantha Mo: 8511745880	PUJAN BUILDCON, B-202, Dev Residency, Nr. Vandematram Flat, Gota, Ahmedabad Mo: 9426004834